

**Mobile farms
for industrial mining**

Specification 40 feet	
Hardware and software complex MAX 3	
Possible number of miners installed	
Antmainer S17/S19	252
Power**,W	3250
Amperage**, A	14,5
Performance characteristics	
Ambient temperature	from -30 to +35
Smooth area for installation of container square meters	100 -135
Power supply 3 phases 380 V, 1st input	465 kW
Power supply 3 phases 380 V, 2nd input	465 kW
Power cable, 1st input, copper, mm sq*, from	2x4x240
Power cable, 1st input, aluminum, mm sq*, from	3x4x185
Power cable, 2nd input, copper, mm sq*, from	2x4x240
Power cable, 2nd input, aluminum, mm sq*, from	3x4x185
Grounding, copper,mm sq*	120
Internet channel min 1 Mbps/sec	2
GSM Internet channel	1
40 ft High Container (High Cube)	
Length, mm	12 192
Width, mm	2 438
Height, mm	2 896
Racks for installing miners, pcs.	
12	
Length, mm	300
Width, mm	1000
Height, mm	2 300
Shelves, units	6
Payload, kg/rack	750
Number of miners on the rack, pcs.	21
Circuit breakers 1p C 20A	252
Power cables for miners 3x1 mm sq., pcs.	504
Power Supply and Automation Shield	
Length, mm	800
Width, mm	400
Height, mm	2 000
Weight, kg	150
Switched current, A	800/800
Power supply voltage	380 V 3P
Management Computer	1
Pressure sensor 0-10 Pa	1
Ventilation	
Axial fan, 11 kW	4
Air valve 1500x1000	8
Air valve 400x2300	4
Frequency converter 30 kW	2
EMI filter 50A	2
Valve actuator 0-10 V	12
Coarse filter	2
Telecommunications	
Mikrotik Router	1
D-link switch 24 port	13
Patch cord Cat 6, pcs.	302
Combined fire detector	
1	
Security camera	
1	
* The precise cable section is determined by responsible power engineer on the Buyer's side	
** Power and Amperage correspond to the <TYPE> column of the device's factory configuration and are maximum for this version of the container.	